

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Mackinac Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 41N R 4W _____ C-2
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

RECEIVED & FILED
 DIANE FRANKOVICH
 MACKINAC COUNTY REGISTRE OF DEEDS

NOV 7 5 1996
 AM _____ PM _____
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	7	8	9	10	11	12	13	14	15	16	17	18
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	18	17	16	15	14	13	12	11	10	9	8	7	6
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie in a field survey on July 11, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845: G.L.O. Survey by J.A. Mullett - Set Post and Referenced
 Sugar 18 - S68E - 29 / Birch 20 - N56W - 28

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found remnants of an old wood stake at the intersection of fencelines East and North.

SURVEY & REMONUMENTATION

MAY 20 1997

COMMISSION

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 8-20-96

James H. Stranger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set 5/8" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner.

Referenced: N60°E - 10" Maple - 2.35 Feet
 North - 15" Beech - 16.35 Feet
 N75°W - 4" Maple - 14.42 Feet
 S42°E - 15" Maple - 23.60 Feet



Signed by *David B. Guthrie*

Date Sept. 30, 1996

Surveyor's Michigan License No. 22435