

1996 Mackinac County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTRE OF DEEDS

For corners in Mackinac (County) Located In: Corner Code #

1. Public Land Survey	T <u>41N</u> R <u>4W</u>	<u>E-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OCT 29 1996
AM PM
7|8|9|10|11|12|1|2|3|4|5|6
A

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on April 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: G.L.O. Survey by J.A. Mullett - Set Post and Referenced Beech 6 - S46E - 20 / Sugar 4 - S18W - 55
- 1957: Survey by MDOT - R.R. Spike 22" below surface.
- 1986: Survey by MDOT - Found N.W. closing corner, 1" Sq. Bolt

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1" Square Iron Bolt.

SURVEY & REMONUMENTATION
MAY 20 1997
COMMISSION

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 8-26-96
James H. Granger

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Set a 5/8" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner placed in a Monument Box.
Referenced: West - 1/2" Iron Rod in Mon. Box - 19.84 Feet
S51°W - Utility Pole - 38.51 Feet
N65°E - 15" Maple - 66.86 Feet
S70°W - 12" Apple - 81.00 Feet



Signed by *D.B. Guthrie* Date Oct. 10, 1996

Surveyor's Michigan License No. 22435 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

E0057