

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Form with fields for 'For corners in Mackinac (County)', 'Located in:', 'Corner Code #', and a table for survey types (Public Land Survey, Property Controlling in Section, Miscellaneous Property in Section) with columns for Town (T), Range (R), and Section (S).

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

NOV 15 1996
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column E and row 3.

I, David B. Guthrie in a field survey on April 17, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845: G.L.O. Survey by J.A. Mullett - Set Post and Referenced Beech 18 - N35E - 31 / Sugar 14 - S15W - 25
1957: Survey by MDOT - 1" Steel Pin in road.
1986: Survey by MDOT - Reset 1/2" Iron Rod from FFS Wit.
1995: Survey by MDOT - Found 1/2" Iron Rod 3.5 Feet East of C.L. gravel Rd., verified 1986 references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1/2" Iron Rod 3.5 Feet East of the centerline of Castle Rock Road.

SURVEY &
REMONUMENTATION

MAY 20 1997


COMMISSION

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 8-20-96

James H. Granger (Signature)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Placed an Aluminum Cap on a 5/8" Iron Rod set 6" below the road surface.
Referenced: N15°E - 2.5' Dia. Rock (drill hole) - 150.02 Feet
N15°W - 6" Spruce - 100.55 Feet
S85°E - 2' Dia. Rock (drill hole) - 175.48 Feet
S68°W - 6" Cedar - 122.70 Feet



Signed by

David B. Guthrie (Signature)

Date

Oct. 1, 1996

Surveyor's Michigan License No. 22435