

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in Mackinac Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 41N R 4W \_\_\_\_\_ G-3  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

**RECEIVED & FILED**  
**DIANE FRANKOVICH**  
 MACKINAC COUNTY REGISTRE. OF DEEDS

NOV 15 1996  
 AM \_\_\_\_\_ PM  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on April 17, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1845: G.L.O. Survey by J.A. Mullett - Set Post and Referenced Beech 12 - N25E - 20 / Sugar 4 - S41W - 29
- 1957: Survey by MDOT - Boat Spike
- 1986: Survey by MDOT - 3/4" Pin in Mon. Box in C.L. Hwy. M-123.
- 1995: Survey by MDOT - Found 3/4" Pin in Mon. Box in C.L. of Hwy. M-123, verified 1986 references.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1996: Found 3/4" Iron Pin in Mon. Box in C.L. of Hwy. M-123.

**SURVEY & REMONUMENTATION**

MAY 20 1997

**COMMISSION**

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELDON 8-20-96

*James H. Dranger*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1996: Placed an Aluminum Cap on a 5/8" Iron Rod in a Monument Box in the centerline of Hwy. M-123.  
 Referenced: N30°E - Drill hole in Culv. ring - 38.19 Feet  
 N40°E - Utility Pole - 54.41 Feet  
 S20°E - 4" Cedar - 58.30 Feet  
 N10°W - Drill hole in Culv. ring - 35.68 Feet  
 South - R.O.W. Mon. - 66.00 Feet



Signed by David B. Guthrie  
 Surveyor's Michigan License No. 22435

Date Oct. 2, 1996