

MAR 13 1998

MACKINAC COUNTY REMONUMENTATION CORNER

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

DEC 29 1997

AM PMA
[8] [9] [1] [2] [3] [4] [5] [6] [7] [8] [9] [0]

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 41N R 3W	A-10
	T _____ R _____	W 1/4 cor. Sec 30
	T 41N R 4W	M-10
	T _____ R _____	E 1/4 Cor, Sec 25
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Neil E. Hill, in a field survey on DECEMBER 22 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840 GLO notes William Burt 4" Cedar N13E 17 lks
4" Cedar S13W 17 lks
 - 1980 L. Feindt set 1" pipe in position of old cedar stake
Recorded Liber B, page 176

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1997 Found 1" pipe. (Old witnesses)
- 1" Bar set by T.L. J. S01W 4.65 feet
 - 1" Bar set b T.L. J. S81E 26.48 feet
 - 6" Cedar N50E 14.07 feet
 - 10" Cedar Stump S15W 11.80 feet
 - 12" Cedar Stump N15E 10.60 feet
- Accepted corner location.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER PA. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" rod with remonumentation cap inside found pipe.
- 8" Cedar S60W 09.05'
 - 10" Spruce N35W 15.66'
 - 10" Cedar N50E 14.02'
 - 6" Spruce S60E 04.87'



Signed by Neil E. Hill P.S. Date DECEMBER 22, 1997
Surveyor's Michigan License No. 27447