

**SURVEY & REMONUMENTATION**

**MAR 13 1998**

**MACKINAC COUNTY REMONUMENTATION CORNER**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>3W</u>	<u>A-11</u>
	T _____ R _____	<u>Sec Cor common</u>
	T _____ R _____	<u>to Sec's 30 &amp; 31</u>
2. Property Controlling in Section	T <u>41N</u> R <u>4W</u>	<u>M-11, Sec Cor common</u>
	S _____ T _____ R _____	<u>to Sec's 25 &amp; 26</u>
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	

RECEIVED & FILED  
DIANE FRADKOVICH  
MACKINAC COUNTY CLERK OF DEEDS

DEC 29 1997

AM PA  
718191101-1111413141516

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Neil E. Hill, in a field survey on DECEMBER 22, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
1845 GLO notes William Burt 4" Cedar S84W 75 lks  
No records of this corner being perpetuated, however various surveys indicate this corner's position  
1977 Survey by C.A. & E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Found 1" iron  
4" W. Birch N60E 45.9' (Face)  
3" W. Birch S60E 40.04' (Face)  
5" Cedar S80W 66.2' (Face)  
3" W. Birch N45W 56.75'  
Accepted corner location.  
Found "T"-iron 220.30' West of Section Corner at Mackinac Trail R.O.W.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-12-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" rerod with remonumentation cap inside found pipe.  
6" W. Birch N60E 45.98' (Side nail)  
5" W. Birch S60E 40.56' (Side nail)  
6" Cedar S80W 66.38' (Side nail)  
5" W. Birch N45W 36.84' (Side nail)



Signed by Neil E. Hill P.S. Date DECEMBER 22, 1997  
Surveyor's Michigan License No. 27447