

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> N. R. <u>1</u> E.	K-5, M-12, I-9
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S. R. _____ E.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S. R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-18-80 I-9, 7-9, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-5 Sec. Cor. 11-12-13-14, set by John Mullett, D.S. in 1845. Bearings were: Sugar 12", N30°W, 30 lks. and Hemlock 18", S32°E, 36 lks.
- M-12 Sec. Cor. 25-36, T42-1E and Sec's. 30-31, 42-2E. Bearings were: Spruce 5", N26°W, 16 lks. and Fir 8", S59°W, 27 lks.
- I-9 Sec. Cor. 22-23-26-27, set by John Mullett, D.S. in 1845. Bearings were: Sugar 14", N53°E, 16 lks. and Iron Wood 10", S75°E, 22 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-5 Found a square concrete monument at corner set by G.F. DeLaMater, R.L.S. in 1947. Found his witnesses; NW Cor. Large Rock, N64½°E, 108.9' and North Cor. 6' long Rock, S8°W, 35.2'. G.F.D.'s notes indicate orig. witnesses. Found two Hard Maple trees which appear to have been blazed as witnesses.
- M-12 Found 5/8" x 24" Iron, set by G.F. DeLaMater, R.L.S. in 1947, by S.P.M. witnesses by a limestone boulder, 36" long, N24°E, 22.6'. Corner lies 20' South of a low ridge and in swamp.
- I-9 Found 4" Concrete Monument, placed by G.F. DeLaMater, R.L.S. in 1947. Re-witnessed monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5 Re-marked witnesses: 15" H. Maple, S30°W, 7.8' & 11" H. Maple, N27°W, 13.9'. Corner lies 40' West of a woods road.
- M-12 Placed 1" pipe with 4" alum. cap at corner. New Bearings: 10" Cedar, N8°W, 29.0' & 9" Cedar, N48°E, 35.3' & 13" Cedar, East, 48.2'.
- I-9 4" Concrete Monument at corner. New Bearings: 12" W. Spruce, S38°E, 7.0' & Twin 6" H. Maple, N66°W, 62.2' & 6" H. Maple, S46°E, 51.4' & 6" H. Maple, N45°E, 68.6

SIGNED BY

*Billy D. Buckler*  
Billy D. Buckler

DATE 7-16-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

