

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>42</u> N. R. <u>1</u> E.	M-10, I-5, M-8, M-9
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3-11 & 3-12, 19 81, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19 _____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-10 1/4 Cor. on East side of Sec. 25, set by Austin Burt, D.S. in 1840. Bearings were: Pine 6", N41°W, 15 lks. and Tam. 10" at corner.
- I-5 Section Corner 10-11-14-15. Bearings were: Fir 12", N36°E and Cedar 6", S13°W, 6 lks.
- M-8 1/4 Cor. on East side of Sec. 24, 42-1E, set by Austin Burt, D.S. in 1840. Bearings were: Pine 8", N49°W, 26 lks. and Pine 6", S22°W, 20 lks.
- M-9 Sec. Cor. 24-25, on East boundary of Township. Bearings were: Spruce 5", N26°E, 6 1/2 lks. and Cedar 4", S70°W, 23 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-10 Found corner set by G.F. DeLaMater, R.L.S. in 1947, by single prop. measure.
- I-5 Found 1" Axle Shaft, buried in road, as found by G.F. DeLaMater, R.L.S. in 1947.
- M-8 Found 4" Concrete Monument, set by G.F. DeLaMater, R.L.S. in 1947. Found original Pine BT in place, N49°W, 26 lks., other Pine BT down.
- M-9 Found Concrete Monument, set by G.F. DeLaMater, R.L.S. in 1947. Found original Cedar BT down.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-10 Re-Witnessed Corner. 12" W. Pine, N78°W, 27.2' & 13" W. Pine, N66°E, 23.1' & 11" W. Pine, S20°W, 13.1'. Corner is buried in a woods road.
- I-5 Recording Corner. Bearings: 40" Boulder, S50°W, 138.4' and South end Culvert, S77°E, 46.0'.
- M-8 Recording this corner. Bearings: Boulder 4' High, Southwest, 12.0' and Boulder 2' High, East, 6.0' and Boulder 2' High, North, 3.0'. Cor. on a side hill, facing to SW.
- M-9 Recording Corner. Bearings: 6" Cedar, West, 17.8' & 6" Cedar, S41°E, 12.2' and 6" Cedar, N57°E, 13.2'.

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 7-15-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

