

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970  
Mackinac Co. 3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 42 N. R. 1 E.	C-4
2. PROPERTY CONTROLL- ING IN SECTION 7	T. 42 N. R. 1 E.	9-Sec. 7, 2-Sec. 7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. R. _____ E.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-5, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
C-4 1/4 Cor. bet. Sec's. 7-8, set by John Mullett, D.S. in 1845. Bearings were:  
Cedar 7", S14°E, 10 lks. & Cedar 9", N46°W, 6 lks.

9-Sec. 7 East 1/16 Corner, Section 7, T42N R1E.

2-Sec. 7 East 1/16 Corner, on North side of Section 7..

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C-4 Corner re-established midway and on line bet. two Section Corners.

9-Sec. 7 Placed corner midway bet. East 1/4 Corner and computed Center, Sec. 7.

2-Sec. 7 Placed corner midway bet. Sec. Cor. to East and computed 1/4 Cor. to West.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 1" pipe with 4" alum. cap at all corners. Bearings:

C-4 8" Spruce, S7°W, 62.2' & 8" W. Birch, S36°E, 37.1' & 8" W. Birch, N17°W, 31.7'.

9-Sec. 7 10" W. Birch, S69°E, 26.4' & 6" W. Birch, S29°W, 22.3' & 8" W. Birch, N88°W, 30.2'

2-Sec. 7 12" Cedar, S74°W, 50.0' & 6" Cedar, N31°E, 44.1' & 8" W. Birch, S75°E, 11.5'

SIGNED BY

Billy D. Buckler  
Billy D. Buckler

DATE 7-14-81

SURVEYOR'S MICHIGAN REGISTRATION NO. - 8887

