

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Mackinac Co. 4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. S., R. <u>1</u> E. <u>W.</u>	G-7, G-6 G-9, H-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. <u>W.</u>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-6 & 7-7, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
Corner set by John Mullett, D.S. in 1845. Bearings were:

G-7 Sec. Cor. 15-16-21-22: Spruce 6", S43°W, 7 lks. & Cedar 6", N34°E, 13 lks.
G-6 1/4 Cor. bet. Sec's. 15-16: Aspen 9", N30°E, 5 lks. & Fir 5", S11°W, 10 lks.
G-9 Sec. Cor. 21-22-27-28: Cedar 10", S54°W, 12 lks. & Tam. 10", N5°E, 34 lks.
H-9 1/4 Cor. bet. Sec's. 22-27: Cedar 24", 16 lks. & Cedar 24", N32°E, 9 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
G-7 Corner re-established by Double Prop. Measure bet. corners; 1 mile North, 1 mile East, 2 miles West, and 2 miles South. Found old blazes on Cedar approx. 100' North as well as other blazes to North.
G-6 Corner re-established midway bet. two Sec. Cors. Corner lies on a Hardwood ridge, as record indicate, found several old blazes in vicinity.
G-9 Re-established corner by Double Prop. Measure bet. Corners; 2 miles North, 1 mile South, 1 mile East, and 1 mile West. Area is Cedar swamp for 300' East, records do not indicate swamp.
H-9 Re-est. cor. midway and on line bet. two Sec. Corners. Numerous large Cedar Stumps in mile.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" alum. cap at all corners. New Bearings:

G-7 10" Cedar, S34°E, 31.4' & 9" Cedar, S24°W, 5.5' & 8" Cedar, NW, 0.5'.
G-6 22" Hemlock, S61°W, 17.0' & 6" S. Maple, N78°E, 26.6' & 5" H. Maple, S19°E, 39.0'.
G-9 12" Cedar, N22°W, 20.3' & 8" Cedar, East, 27.8' & 13" Cedar, S9°W, 20.5'.
H-9 20" Cedar Stump, S54°E, 10.5' & 9" W, Spruce, S41°E, 5.4'. Corner set with pile of limestone rocks.

SIGNED BY

Billy D. Buckler
Billy D. Buckler

DATE 7-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

(SEAL)