

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

4 Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>42</u> N. R. <u>1</u> E.	<u>E-9, I-7, D-3</u>
2. PROPERTY CONTROLLING IN SECTION	<u>8</u> T. <u>42</u> N. R. <u>1</u> E.	<u>1-Sec.8</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. R. _____ E.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-4-80 & 2-5-81, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Sec. and 1/4 Cors. set by John Mullett, D.S. in 1845. Bearings were:

- E-9 Sec. Cor. 20-21-28-29: W. Pine 16", S13°W, 18 lks. and Fir 8", N23°E, 5 lks.
 I-7 Sec. Cor. 14-15-22-23: Tam 18", N78°E, 21 lks. and Tam 16", S82°W, 15 lks.
 D-3 1/4 Cor. bet. Sec's. 5-8: Sugar 6", S40°W, 12 lks. and Aspen 9", N32°E, 8 lks.
 1-Sec.8 West 1/16 Corner, Section 8, 42-1E.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-9 Replaced corner from W. Pine Bearing tree, a stump in good condition with scribe marks evident on bottom blaze, with notch.
 I-7 Re-witnessed corner as set by G.F. DeLaMater, R.L.S. in 1947. Found 4" X 4" Concrete Monument, 8" above ground level.
 D-3 Re-established corner midway and on line bet. two Section Corners.
 1-Sec.8 Placed corner midway bet. Section Corner to West and 1/4 Corner to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-9 Placed Cedar Post at corner. New Bearings: 8" Cedar, S21°E, 25.8' & 6" Cedar, S73°W, 36.0' & 14" W. Pine, N73°W, 41.9'.
 I-7 4" Concrete Monument at corner. New Bearings: 8" W. Spruce, N76°W, 100.4'. Monument lies on East edge of a N-S Grade and in line with Grade to West.
 D-3 Placed 1" pipe with 4" alum. cap at corner. New Bearings: 6" Cedar, N65°E, 62.6' & 10" Spruce, S41°W, 46.1' & 6" R. Maple, S67°W, 10.8'.
 1-Sec.8 Placed 1" pipe with 4" alum. cap at corner. Bearings: 8" R. Maple, N36°E, 17.0' & 8" R. Maple, S48°E, 35.9'.

SIGNED BY

Billy D. Buckler
 Billy D. Buckler

DATE 7-8-81

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

