

MAR 20 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T42N R01E	F-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTRAR OF DEEDS

FEB 25 2000

AM PM
11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Neil E. Hill, in a field survey on 12-20-99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1845 GLO Notes J Mullett 10" Spruce N 30 E 15 lks
8" Aspen S 31 W 06 lks
- 1976 Reino Alanen * No witnesses listed
Fd 1" Pipe in CL Swede Rd.
Pipe agrees with N-S fences
Liber A, Page 187

No Subsequent Information

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-10-99
Neil E. Hill

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1999 Fd 1" Pipe in CL of Swede Rd
Accepted corner location
Placed 4" Alum remonumentation Cap and monument box (Spring 2000)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner is 1" rod with 4" Alum remonumentation Cap
- Corner is in CL of Swede Rd
- Fence Post Due S 34.02'
- Pwr Pole N 10 E 37.24'
- Pwr Pole S 45 W 30.07'
- 2" Tree S 20 E 37.54' Clump of small trees, Easterly 2" tree



Bearings are compass bearings, corrected for declination, all distances are to a double-head nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S.P.C. Date January 21 2000

Surveyor's Michigan License No. 27447