

**MAR 20 2000**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**Mackinac County Remonumentation Corner**

For corners in

| Mackinac County                    | Located in: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey              | T42N R01E   | H-5           |
|                                    | T R         |               |
|                                    | T R         |               |
|                                    | T R         |               |
| 2. Property Controlling in Section | S T R       |               |
|                                    | S T R       |               |
| 3. Miscellaneous Property in Sec.  | S T R       |               |
|                                    | S T R       |               |
| 4. Lot No. , Recorded Plat         |             |               |
| 5. Private Claims                  |             |               |

**RECEIVED & FILED**  
**DIANE FRANKOVICH**  
 MACKINAC COUNTY REGISTER OF DEEDS

**FEB 25 2000**

AM PM  
 1/31/10/11/12/13/14/15

**Register of Deeds Stamp & File Number**

I, Neil E. Hill, in a field survey on 12-20-99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 3  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    | ● |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |    |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

*T42N R01E*

**A. Description of original monument and accessories and/or subsequent restoration:**

|                                   |           |        |        |
|-----------------------------------|-----------|--------|--------|
| 1845 GLO Notes J Mullett          | 30" Sugar | S 43 W | 10 lks |
| 1996 Ronald Bischer               | 5" Maple  | N 14 W | 19.31' |
| Set 1/2" rod by single proportion | 4" Maple  | S 74 E | 8.82'  |
| Liber E Page 042                  | 8" Maple  | Due S  | 9.30'  |
|                                   | 5" Maple  | S 80 W | 31.08' |
|                                   | Fence     | Due W  | 7.5'   |
|                                   | CL Road   | Due N  | 56.0'  |

**ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON** 12-10-99

*Neil E. Hill*

**No Subsequent Information**

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1999 Fd 1/2" rod in can next to 4" wood post  
 Accepted corner location  
 Placed 4" Alum. remonumentation cap

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is 1/2 rod with 4" Alum remonumentation cap  
 Corner is approx 56' South of CL Swede Rd

|          |        |        |                               |
|----------|--------|--------|-------------------------------|
| 6" Maple | N 15 W | 19.28' | old 1/2" pipe next to witness |
| 6" Maple | S 75 E | 8.80'  |                               |
| 9" Maple | Due S  | 9.17'  |                               |
| 7" Maple | S 80 W | 30.90' |                               |



Bearings are compass bearings, corrected for declination, all distances are to a double-head nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S.P.C.

Date January 21 2000

Surveyor's Michigan License No. 27447