

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 20 2000

Mackinac County Remonumentation Corner

SECTION

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T42N R01E	K-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS

FEB 25 2000

AM PM
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	J	K	L	M
1												
2	3			5		4		3		2		1
3												
4	7			8		9		10		11		12
5												
6	18			17		16		15		14		13
7												
8	19			20		21		22		23		24
9												
10	30			29		28		27		26		25
11												
12	31			32		33		34		35		36
13												

I, Neil E. Hill, in a field survey on 12-20-99, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes William Brt	8" Spruce	S 01 W	20 lks
	8" Spruce	S 22 E	21 lks
1987 William Karr	Pwr Pole	S 05E	139.70'
Fd 1" pipe in wood post	"X" in rock	S 60 W	30.17'
Accepted corner location	USGS BM	S 35 W	47.20'
Liber C Page 243	Pwr Pole	N 77 E	109.23'

ACCEPTED BY THE MACKINAC COUNTY
SURVEY PEER GROUP AS THE
OFFICIAL CORNER UNDER P.A.
345 OF 1990 AT A MEETING
HELD ON 12-20-99
Neil E. Hill

No Subsequent Information


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999 Fd Corner and 1 witness
Accepted corner location, placed 4" Alum. remonumentation cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1" pipe with 4" Alum remonumentation cap
Corner is on the North Mackinac County Line
Corner is in the northern section of an intersection of gravel roads to the North, East and South

USGS BM	S 35 W	47.10'
Ancher Post	N 50 E	58.04'
Meter Pole	N 65 E	87.05'
Gate Post	N 65 W	44.91'



Bearings are compass bearings, corrected for declination, all distances are to a double-head nail in the side of the witness object unless otherwise noted.

January 21 2000

Signed by Neil E. Hill D.S.P.C.

Date _____

Surveyor's Michigan License No. 27447