

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|------|-----------|-------|
| 1. Public Land Survey | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| | T | R | _____ |
| 2. Property Controlling in Section | S 22 | T 42NR 1E | 16 |
| | S | T R | _____ |
| 3. Miscellaneous | S | T R | _____ |
| Property in Sec. | S | T R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

May 02 2001

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (16-Sec. 22) East 1/16 corner between Sections 22 and 27. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(16-Sec. 22) Established the corner midway and on a line of mean true bearing between Quarter corner 1304.03' west and Section corner 1304.03' east. An east-west trail is 18' south of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(16) Set 1" IDx36" iron pipe with 4" aluminum MDNR tablet. Blazed, scribed, and set measuring nails in:
 5" Balsam S75E 4.7' "E1/16 NBT"
 5" Balsam S32E 4.9' do
 10" Balsam S50W 31.8' do
 5" Balsam N40E 43.5' do
 Set squared cedar post adjacent.
 Bearings are magnetic. Distances to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/16/81

For the Michigan Department of Natural Resources - Office of Property Management