

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>14</u> T <u>42N</u> R <u>1E</u>	<u>8</u>
	S <u>14</u> T <u>42N</u> R <u>1E</u>	<u>J6</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on J6 02/08/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- (8-Sec. 14) West 1/16 corner, Section 14. Not established in the original survey.
- (J6) Center of Section 14. Not established in the original survey.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- (8-Sec. 14) Established the corner midway and on a straight line between Quarter corner 1335.80' west and Center of Section 14 1335.80' east.
- (J6) Established the corner at the intersection of straight lines connecting opposite Quarter corners. From the position thus established I found a 1/2" rebar with cap #22428 (R.Bischer PS), not of record, S24W 2.28' distant, which I did not accept as marking the position for the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |   |   |
|---|---|
| (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br>5" Balsam N02E 9.2' mrkd "W1/16 BT"<br>14" W.Spruce S84E 20.95' do<br>9" Balsam S01E 16.15' do<br>16" W.Spruce S68W 13.15' do<br>Bearings are magnetic. | (J6) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:<br>6" W.Birch S27E 11.4' mrkd "CS BT"<br>5" Balsam S64W 9.0' do<br>7" Balsam N75E 13.25' do<br>1/2" capped rebar S24W 2.28'<br>Bearings are magnetic. |
|---|---|

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/20/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division

47359  
47360