

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 1E	I5
	T 42N R 1E	K5
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Stephan J. Szyszkoski, in a field survey on K5 07/09/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I5) Corner common to Sections 10-11-14-15. 1999 - Record of Neil E. Hill PS accepted by the Mackinac County Remonumentation Program. 1/2" rod with 4" aluminum remonumentation cap. 10" twin Birch N10W 25.45', 8" Cedar S41W 46.98', 10" Cedar S15E 26.70', 8" Poplar S10W 19.51', 1" pipe Due North 2.00'. Recorded in Book E Page 371.

(K5) Corner common to Sections 11-12-13-14. 1947 - Remonumented by G.F.DeLaMater RLS who set a concrete monument at the corner position. 1981 - Record of Billy D. Buckler RLS: Found a square concrete monument at corner set by G.F.DeLaMater, R.L.S. in 1947. Found his witnesses; NW Cor. Large Rock N64 1/2E, 108.9' and North Cor. 6' long Rock, S8W 35.2'. G.F.D.'s notes indicate orig. witnesses. Found two Hard Maple trees which appear to have been blazed as witnesses. Re-marked witnesses: 15" H.Maple S30W 7.8' and 11" H.Maple N27W 13.9'. Corner lies 40' west of a woods road.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I5) The Mackinac County remonumentation monument was found disturbed, bent and with aluminum cap missing. I removed the monument and in its place, at record bearing and distance from the 1999 accessories, all present, drove a new monument.

(K5) Found a 1/2" rebar encased in a 4" square concrete monument, in good condition, and at record bearing and distance from the 1981 H.Maple witnesses, both in good condition. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I5) Set 5/8"x24" rebar with plastic cap "Mich DNR LS33986". Set measuring nail with MDNR tag in the side of: 10" Cedar S60E 56.02' mrkd "S14 NBT" 11" Cedar S14E 26.63' do 11" Cedar S42W 46.71' "S15 NBT" Fence post N08E 37.76' 10" twin Birch N10W 25.45' fd. nail 1" pipe North 2.0' Bearings are magnetic.	(K5) Found 1/2" rebar in 4" square conc. mon. Set measuring nail with MDNR tag in the side of: 16" Sugar N24W 14.2' mrkd "S11" 1981 NBT 21" Sugar S30W 8.45' "S14" do 10" Sugar S50E 24.2' mrkd "S13 NBT" 12" Sugar N60E 43.05' "S12 NBT" Bearings are magnetic.
--	---

Signed by Stephan J. Szyszkoski Date 05/20/2010
 Surveyor's Michigan License No. 33986



For the Michigan Department of Natural Resources and Environment, Forest Management