

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 1E	L3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 08/18/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L3) Quarter corner common to Sections 1 and 12. 1845 - Established by John Mullett Deputy Surveyor midway and on the Section line between Section corners 39.94 chains east and west. Set post on true line. Spruce 8" N77W 22 links, Spruce 8" S80E 5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L3) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner midway and on the Section line between Section corners 2642.29 ft. east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" Cedar N17E 2.05' mrkd "1/4S NBT"
 7" Cedar S80E 1.35' do
 7" Cedar S14W 16.55' do
 11" Cedar N61W 22.35' do
 Bearings are magnetic. The mon. leans to the south. The center of the cap marks the corner position.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/26/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities