

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

| | | |
|---------------------------------------|-------------------------|---------------|
| <u>Mackinac</u> (County) | Located In: | Corner Code # |
| 1. Public Land Survey | T 42N R 1E | K4 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S 12 T 42N R 1E | 10 |
| | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | ● | 12 | | |
| 5 | | | | | | | | | | ● | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Stephan J. Szyszkoski, in a field survey on 10 06/22/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K4) Quarter corner common to Sections 11 and 12. 1845 - Established by John Mullett Deputy Surveyor midway and on the Section line between Section corners 40.00 chains north and south. Set post. Cedar 12" N51E 13 links, Spruce 9" S56W 20 links. Found no subsequent record.

(10-Sec. 12) South 1/16 corner between Sections 11 and 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K4) The original post and accessories were not recovered. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the corner position midway and on the Section line between Section corners 2668.77 ft. north and south.

(10-Sec. 12) Established the corner midway and on the Section line between Section corner 1334.38' south and Quarter corner 1334.38' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 7" Cedar S62W 20.4' mrkd "1/4S NBT"
 7" W.Birch S51E 2.2' do
 5" Cedar N32W 9.6' do
 9" Cedar N30E 14.65' do
 Bearings are magnetic.

(10) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" Cedar N20E 12.35' mrkd "S1/16 BT"
 10" Cedar N65E 15.75' do
 9" twin Cedar N51W 26.55' do
 8" Spruce S06W 36.0' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/26/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

