

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 12 T 42N R 1E _____	15
	S 12 T 42N R 1E _____	11
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 15 06/22/2009 and 11 07/09/2009 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (15-Sec. 12) West 1/16 corner between Sections 12 and 13. Not established in the original survey.
- (11-Sec. 12) Southwest 1/16 corner, Section 12. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (15-Sec. 12) At the position for the corner, midway and on the Section line between Section corner 1324.35' west and Quarter corner 1324.35' east, I found a 1/2" dia capped rebar, set flush, markings on cap not readable. Accepted same as a careful and faithful establishment of the position of the corner
- (11-Sec. 12) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| (15) Found 1/2" rebar w/unreadable plastic cap. Set measuring nail with MDNR tag in the side of:
6" Balsam S65E 7.65' mrkd "W1/16 BT"
7" Balsam S26E 10.6' do
10" Balsam S85W 31.85' do
8" Balsam N10W 23.45' do
Bearings are magnetic. | (11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
10" twin Maple S27W 14.8' mrkd "SW1/16 BT"
7" Maple N30W 17.8' do
8" Maple North 12.9' do
10" Balsam S47E 3.4' do
Bearings are magnetic. |
|--|---|

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 08/26/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities