

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 NR. 1 W. . . .

Mackinac

----- COUNTY

DESCRIPTION OF CORNER Meander Corner between Sections 9-16 on East Shore at
Bay City Lake.

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap -----

WITNESSES TO CORNER ----- 13" Cedar N 28° W 36 links
----- Marked "M.C." NBTM -----

----- 12" W. Pine N 41° E 87 links
----- Marked "M.C." NBTM -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

No evidence of original corner.

Re-established Meander Corner by proportionate measure between Section
Corner 8, 9, 16, 17 and 1/4 Corner between Sections 9/16 as per:
Gov't Field Notes.

Corner established and witnessed November 8, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/21/56
REGISTERED LAND SURVEYOR