

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42. NR. 1 W. . . .

Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 8, 9, 16, 17 . .

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER 5" Red Oak S 15° W 13 links
Marked " S 17° NBT"

6" Red Oak N 88° E 22 links
Marked " S 9° NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established Section Corner by double proportionate measure from:

Section Corner	1 mile	West
Section Corner	1 mile	South
1/4 Corner	1/2 mile	East
County Road	1 mile	North

No evidence of original corner.

Corner established and witnessed November 8, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/21/56
REGISTERED LAND SURVEYOR