

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 NR. 1 W.

Mackinac

COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sec.'s 17-18

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 10" W. Spruce S 59° E 70 links

Marked "1/4 S NBT"

10" Aspen N 53° E 58 1/2 links

Marked "1/4 S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established 1/4 corner midway and on line between two Section Corners.
No evidence of original corner which was 6" aspen.

Found 4" square concrete monument N 12° E 170 links. No supporting evidence.

1/4 Corner lies 1.83 chs. west of power line.

SURVEYORS SEAL

SIGNED

REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/2/57