

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 42. NR. 1 W.

Mackinac COUNTY

DESCRIPTION OF CORNER Section Corner common to Sec.'s 17-18-19-20

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 15" Red Pine S 17° W 115 links

Marked "S 19 NBT"

8" W. Pine N 52° E 59 links

Marked "S 17 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from W. Pine B.T. bearing N 38° W 13 links.  
Bottom of stump remain. Found part of notch and bearing blaze.  
Stump badly burned.

Found recent stake in place, also in clay soil found remains of older stake.

Corner lies on south edge of old E-W logging R.R. grade. This grade runs along line the entire mile east.

SURVEYORS SEAL

SIGNED

Billy J. Buckles  
REGISTERED LAND SURVEYOR

DATE 4/30/57