

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N. R. 1W


Mackinac COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 23-24-25-26

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7-27-70

WITNESSES TO CORNER..... 8" cedar (S 23 NBT) N49°W 18.6'



8" cedar (S 23 NBT) N4°W 17.8'

AND

SINGLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced this corner at an old, squared, wood post. Found several stake bottoms in the ground at this point.

Found two cedars marked with a blaze and notch, as witnesses, to this corner. Trees were marked about 1932 (determined by annual ring count). Both are now 9" in diameter. Trees bear S85°W 7.0' and N13°W 8.3'.

Distances to north, south and west to swamp edges, check with the record distance.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8-4-70
REGISTERED LAND SURVEYOR