

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 1W


Mackinac COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 15-22

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5-18-70

WITNESSES TO CORNER..... 9" Cedar (1/4 S NBT) N45°E 33.0'



8" Cedar (1/4 S NBT) S 09°W 25.4'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at a squared cedar post, set by unknown persons. Found an old rail fence to west, in line with this corner. Fence appears to be on south edge of a small clearing. Clearing is partially grown in with small trees. Corner lies 100' S.E. of the open clearing and on N.W. edge of a cedar swamp.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-4-70
REGISTERED LAND SURVEYOR