

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N. R. 1W


Mackinac COUNTY

DESCRIPTION OF CORNER ½ Corner bet. Secs. 22-23

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5-18-70

WITNESSES TO CORNER..... 8" Cedar (½ S NBT) S 1° W 30.7'



7" Cedar (½ S NBT) N 77° W 12.8'

8" Cedar (½ S NBT) East 3.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established midway and on line bet. two Sec. Cors. Found no evidence of original corner.

Distance south to stream is close to record. Stream is now a flooded beaver dam.

Corner lies in thick cedar swamp 70' north of wet tamarack and cedar swamp and is 100' east of an old log road.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 8-4-70