

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION _____, T. _____	22 42 N. S., R. _____ E. W.	1, 3, 4
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____	N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David E. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 4-28 & 5-4, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

West 1/16 Cor. on North side of Sec. 22. Not prev. est.

North 1/16 cor. on West side of Sec. 22. Not prev. est.

Northwest 1/16 cor. of Sec. 22. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set M.P.O.I. between the NW sec. cor. and the North 1/4 cor. of section 22.

Set M.P.O.I. between the NW sec. cor. and the West 1/4 cor. of section 22.

Set at the center of the NW 1/4 of sec. 22 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument. Bearings:	3	1" pipe. Bearings:	4	D.N.R. Monument. Bearings:
8" W. Pine, N19°E, 5.4'		12" W. Pine, S45°E, 76.9'		8" Cedar, S27°E, 8.5'
10" W. Pine, S30°W, 32.1'		14" Cedar, N82°E, 74.6'		8" Cedar, East, 7.8'
8" Cedar, S05°E, 23.55'		8" Cedar, S53°W, 59.8'		6" Cedar, N53°E, 6.65'
10" Cedar, S68°E, 17.0'		5" Cedar, S70°W, 55.7'		6" Cedar, N15°W, 20.2'

Cor. lies 3' West of center line.

SIGNED BY

*David E. Babbitt*  
 David E. Babbitt

DATE 8-3-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_