

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Mackinac Co.

2 Corners.

#27

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 42 N. <u>1W</u> S. R. <u>7</u> W.	H-9
2. PROPERTY CONTROLLING IN SECTION <u>22</u>	T. 42 N. <u>1W</u> S. R. <u>7</u> W.	15
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-4, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9 1/4 cor. on south side of sec. 22. Wood Post, Cedar 4", N61°W, 18 lks. & Fir 6", S30°E, 7 lks.
- 5 West 1/16 cor. on south line of sec. 22. Not prev. est.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9 Set M.P.C.L. between the SW sec. cor. and the SE sec. cor. of sec. 22. No original evidence found.
- 5 Set M.P.C.L. between the SW sec. cor. and the South 1/4 cor. of sec. 22.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9 D.N.R. Monument. New Bearings:
 - 10" Cedar, S70°E, 19.7'
 - 8" Cedar, S30°W, 4.7'
 - 6" Cedar, N53°W, 10.3'
 - 10" Cedar, N53°E, 18.5'
- 15 D.N.R. Monument. Bearings:
 - 5" W. Pine, S40°E, 54.5'
 - 6" W. Pine, S72°E, 38.1'
 - 6" Spruce, N17°E, 20.9'

SIGNED BY David B. Babbitt
David B. Babbitt

DATE 8-3-82

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: