

#22

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	42N	R	1W	K7
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on July 26, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3	14	15	16	17	18	19	20	21	22	23	24	25	26
4	27	28	29	30	31	32	33	34	35	36	37	38	39
5	40	41	42	43	44	45	46	47	48	49	50	51	52
6	53	54	55	56	57	58	59	60	61	62	63	64	65
7	66	67	68	69	70	71	72	73	74	75	76	77	78
8	79	80	81	82	83	84	85	86	87	88	89	90	91
9	92	93	94	95	96	97	98	99	100	101	102	103	104
10	105	106	107	108	109	110	111	112	113	114	115	116	117
11	118	119	120	121	122	123	124	125	126	127	128	129	130
12	131	132	133	134	135	136	137	138	139	140	141	142	143
13	144	145	146	147	148	149	150	151	152	153	154	155	156

A. Description of original monument and accessories and/or subsequent restoration:

(K7) Corner common to Sections 13-14-23-24. Corner previously restored in 1970 by Billy D. Buckler RLS as follows: 1" pipe with 4" aluminum cap. Witnesses to corner: 12" Hard Maple (NBT) S10E 78.6', 12" W. Spruce (NBT) N46W 29.4', 14" W. Birch (NBT) N5E 49.2'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K7) Buckler's pipe was not recovered, apparently removed by unknown parties. Found a "t" iron below the surface of a raised roadway, at record bearing and distance from Buckler's bearing trees, The maple and spruce being dead, and the W. Birch a cut stump. Scribing was evident on all of the 1970 NBTs. Placed a 1"x32" iron pipe with a plastic cap stamped "MICH DNR LS 33986" directly over the "t" iron and marked two new bearing trees. Also recovered two NBTs marked by T.L. Fabis, RLS 31591.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K7) Set 1" pipe with cap over "t" iron
Blazed, scribed, and placed measuring
nails with tags in the following new
bearing trees:
5" Balsam South 52.9'
3" Balsam N03W 20.3'
Found tag #31591 in the following:
12" Spruce S07E 53.1'
10" Aspen N53E 55.4'
Bearings magnetic.



Signed by

Stephan J. Szyszkoski

Date

1-27-94

Surveyor's Michigan License No.

33986