

SURVEY & REMONUMENTATION

JAN 21 1999

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T42N R01W	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

RECEIVED & FILED
DIANE FRANKOVICH
 MACKINAC COUNTY REGISTER OF DEEDS
 DEC 31 1998
 AM P.M.
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Neil E. Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes J Mullett	10" Tamarack	S 68 E	39 Iks
	6" Tamarack	N 68 W	25 Iks
1950's MSHD Plans 3/4" rod 24.7' South of CL M-134			
1993 R Bischer	CL M-134	Due North	24.70'
Fd 3/4" Rod	R/W Marker	Due N	99.70'
Liber D, Page 247	12" Spruce	S 06 W	63.05'
	14" Spruce	N 11 W	83.75'

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-04-98 NEH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd 3/4" rod and 3 witnesses
 Accepted corner location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is 3/4" rod
 Corner is approx 25' South of CL of M-134

R/W Marker	Due North	99.70'
12" Spruce	S 06 W	63.08'
12" Spruce	S 25 E	53.34'
12" Cedar	S 50 W	84.73'



Bearings are compass bearings, corrected for declination, all distances are to a double-headed nail in the side of the witness object unless otherwise noted.

Signed by Neil E Hill P.S. Date 12-29-98

Surveyor's Michigan License No. 27447