

**SURVEY & REMONUMENTATION**

MAR 13 1998

1997 MACKINAC COUNTY REMONUMENTATION CORNER

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Mackinac County  
(County)

Located In:

Corner Code #

- |                                      |   |            |   |           |              |       |
|--------------------------------------|---|------------|---|-----------|--------------|-------|
| 1. Public Land Survey                | T | <u>42N</u> | R | <u>1W</u> | <u>F-1</u> ✓ |       |
|                                      | T | <u>43N</u> | R | <u>1W</u> | <u>F-13</u>  |       |
|                                      | T | _____      | R | _____     | _____        |       |
|                                      | T | _____      | R | _____     | _____        |       |
| 2. Property Controlling in Section   | S | _____      | T | _____     | R            | _____ |
|                                      | S | _____      | T | _____     | R            | _____ |
| 3. Miscellaneous Property in Section | S | _____      | T | _____     | R            | _____ |
|                                      | S | _____      | T | _____     | R            | _____ |

RECEIVED & FILED  
DEC 11 1997  
MACKINAC COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David Guthrie, in a field survey on September 24, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1840: GLO Survey by Wm. Burt - Set post and referenced:  
Sugar 6/N67°E/11  
Sugar 6/N41°W/33

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 12-19-97

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Remonumentation Survey by R. S. Scott Associates, Inc.  
Found 3/4" Iron Pipe - Referenced:  
S46°W - 4" Maple - 30.10'  
(Exist.) S24°E - Utility Pole - 41.87'  
(Exist.) N37°E - Utility Pole - 43.82'  
(Exist.) N05°W - 10" Maple - 21.17'

This corner position is compatible with county and local surveys. This corner position is accepted as a faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed 3" Mackinac County cap stamped to identify the corner over the 1/2" iron rod. Referenced:  
S46°W - 4" Maple - 30.10'  
S24°E - Utility Pole - 41.87'  
N37°E - Utility Pole - 43.82'  
N05°W - 10" Maple - 21.17'



Signed by David B. Guthrie

Date 12-19-97

Surveyor's Michigan License No. 22435