

# SURVEY & REMONUMENTATION

MAR 13 1998

## 1997 Mackinac County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42NR 1W T 43NR 1W	G-1 ✓ G-13
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED & FILED  
MACKINAC COUNTY REGISTER OF DEEDS  
DEC 31 1997  
AA  
7181214-11-13181816

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David B. Guthrie, in a field survey on July 18 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:  
1840: G.L.O. Survey by Wm. Burt - Set Post and Referenced -  
Sugar 10 / N41E / 24  
Sugar 18 / N48W / 33  
1982: Survey by Wm. L. Karr - Found and accepted 1/2" Iron Pin.  
Referenced -  
N81°W - 6" Maple - 84.72'  
S53°W - 8" Maple - 94.18'  
S89°E - 12" Maple - 56.80'  
S46°E - U. Pole - 49.01'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Remonumentation Survey by R.S. Scott Associates, Inc.  
Found 3/4" Iron Rod 4' E. of C.L. of Road.  
Referenced -  
(Exist.) S45°E - Utility Pole - 49.13'  
S85°E - 16" Maple - 56.82'  
S50°W - 8" Maple - 80.85'  
(Exist.) N75°W - 10" Maple - 84.80'  
This corner position is compatible with County and local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER P.A. 345 OF 1990 AT A MEETING HELD ON 11-21-97

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1997: Placed 3" Mackinac County Cap stamped to identify the corner over 1/2" Iron Rod in Monument Box.  
Referenced -  
(Exist.) S45°E - Utility Pole - 49.13'  
S85°E - 16" Maple - 56.82'  
S50°W - 8" Maple - 80.85'  
(Exist.) N75°W - 10" Maple - 84.80'



Signed by David B. Guthrie  
Surveyor's Michigan License No. 22435

Date: 12-19-97