

SURVEY & REMONUMENTATION

JAN 21 1999

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

Mackinac County Remonumentation Corner

For corners in

Mackinac County	Located in:	Corner Code #
1. Public Land Survey	T42N R01W	G-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

**RECEIVED & FILED
DIANE FRANKOVICH
MACKINAC COUNTY REGISTER OF DEEDS**

DEC 31 1998
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Neil E. Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes J Mullett	6" Maple	S 32 W	5 lks
	6" Beech	N 48 E	11lks
1994 R Bischer	Tel Pole	S 29 W	68.05'
Set 1/2" Rod by	4" Maple	S 45 W	64.26
Single proportion	3" Maple	S 67 W	73.45'
Liber D, Page 263	3" Birch	S 88 W	75.83'

1997 R.S.Scott Associates Fd 1/2" Rod
Remonumentation peer group held over corner due to lack of information

ACCEPTED BY THE MACKINAC COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER PA. 345 OF 1990 AT A MEETING HELD ON 12-04-98 NEH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd 1/2" re-rod in mon box severely bent and 3 witnesses
Straightened corner from existing witnesses
Accepted corner location
Placed 4" Alum. remonumentation cap



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rered in mon box with 4" Alum. remonumentation cap
Corner is on the CL of 3-Mile Rd

1/2" re-rod	Due W	33.00'	
Pwr Pole	S 29 W	68.05'	(Pole cut off 4' high, witness nail in rear, NOT PK nail on roadside)
3" Maple	S 67 W	73.45'	
3" Birch	S 88 W	75.83'	

Bearings are compass bearings, corrected for declination, all distances are to a double-headed nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S. Date 12-29-98

Surveyor's Michigan License No. 27447