

**SURVEY & REMONUMENTATION**

JAN 21 1999

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SECTION**

**Mackinac County Remonumentation Corner**

For corners in

Mackinac County Located in: Corner Code #

1. Public Land Survey T42N R01W **J-1** ✓  
 T43N R01W J-13  
 T R  
 T R  
 2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

4. Lot No. , Recorded Plat  
 5. Private Claims

**RECEIVED & FILED**  
**DIANE FRANKOVICH**  
 MACKINAC COUNTY REGISTER OF DEEDS

DEC 31 1998

AM PM  
 7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

I, Neil E Hill, in a field survey on 12-21-98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1845 GLO Notes James Mullett	8" Tamarack	N 72 E	7 lks
	16" Birch	N 44 W	11 lks
1970 DNR Billy Buckler	12" Cedar	S 62 E	30.5'
Set 1" pipe and DNR cap	7" Cedar	Due N	27.5'
From original BT			
Liber 2, Page 638			
1992 S Kass	7" Cedar	Due N	27.10'
Fd 1" pipe and broken cap	20" Hemlock	S 56 E	24.50'
Liber D, Page 163	14" Hemlock	S 35 W	24.54'
	8" Cedar	N 59 E	27.63'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1998 Fd 1" pipe, broken cap and 4 witness trees  
 Original Y Birch BT is now up-rooted and down to NW  
 Accepted corner location

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is 1" pipe with a broken DNR cap  
 Corner is on North edge of E-W snowmobile trail  
 Corner is partially protected by rootball of downed BT

7" Cedar	Due N	27.10'	(Old)
20" Hemlock	S 56 E	24.50'	(Old)
14" Hemlock	S 35 W	24.54'	(Old)
8" Cedar	N 59 E	27.63'	(Old)

Bearings are compass bearings, corrected for declination, all distances are to a 20 penny nail in the side of the witness object unless otherwise noted.

Signed by Neil E. Hill P.S.

Date 12-29-98

Surveyor's Michigan License No. 27447

