

# SURVEY & REMONUMENTATION

MAR 13 1998

## 1997 Mackinac County Remonumentation Corner LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

### SECTION

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 42NR 1W T 41NR 1W	<u>L-13</u> ✓ <u>L-1</u>
2. Property Controlling in Section	T ___ R ___ S ___ T ___ R ___	_____ _____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____ _____

RECEIVED & FILED  
DIANE H. PLATT  
MACKINAC COUNTY REGISTER OF DEEDS  
DEC 31 1997  
AM PM  
[18] [19] [20] [21] [22] [23] [24] [25] [26] [27] [28] [29] [30] [31] [32] [33] [34] [35] [36]

Register of Deeds Stamp & File Number.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, David B. Guthrie, in a field survey on Dec. 16, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
1840: Survey by Wm. A. Burt - Set Post and Referenced

1973: Survey by Mary C. Fientdt - Found 1/4" solid Rod Liber A Pages 095-096

1978: Survey by Lawrence R. Fientdt - Found 1/4" rod, reset with "T" iron.

1984: Survey by William L. Karr - Found "T" iron

1990: Survey by William L. Karr - Found "T" iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Remonumentation survey by R.S. Scott Associates, Inc.

This corner position is compatible with County and local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 12-29-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed a 3" Mackinac County Cap stamped to identify the corner over 1/2" Iron Rod, over "T" iron, in Monument Box.

Referenced -

N80°E - 78.48' - P.P.

(Exist.) Tag#22428 - S05°E - 87.34' - P.P.

(Exist.) Tag#22428 - N80°W - 98.87' - P.P.

S58°W - 83.58' - 14" Poplar



Signed by D.P.B. [Signature]  
Surveyor's Michigan License No. 22435

Date: 12-22-97