

**SURVEY &  
REMONUMENTATION**

MAR 13 1998

**SECTION**

1997 Mackinac County Remonumentation Corner  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac  
(County)

Located In:

Corner Code #

1. Public Land Survey

T42N R 1W

M-1 ✓

T43N R 1W

M-13

Township corner

T42N R 1E

A-1

T43N R 1E

A-13 Chippewa co.

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

**RECEIVED & FILED**  
DIANE PRAL KOVICH  
REGISTER OF DEEDS

DEC 31 1997

AM PMA  
7/8/97 10:51:56

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, David B. Guthrie, in a field survey on Dec. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	19			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

1840: G.L.O. Survey by Wm. A. Burt - Set Post and Referenced

1975: L.C.R.C., Liber C, Page 165: Found 1" Sq. bolt in well box.

1991: MDOT notes: Found boat spike

1992: Survey by Neil Hill: Found boat spike in Monument Box.

Liber D Page 138

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997: Remonumentation Survey by R.S. Scott Associates, Inc.

Found boat spike .

This corner position is compatible with County and local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

ACCEPTED BY THE MACKINAC COUNTY  
SURVEY PEER GROUP AS THE  
OFFICIAL CORNER UNDER P.A.  
345 OF 1990 AT A MEETING  
HELD ON 12-19-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1997: Placed a 3" Mackinac County Cap stamped to identify the corner over 1/2" Iron Rod, over boat spike in Monument Box.

Referenced-

(Exist.) Tag#3920 - N40°W - 91.75' - 12" Cedar

(Exist.) MDOT Tag - S55°W - 68.48' - 6" Cedar

(Exist.) MDOT Tag - N60°E - 84.98' - P.P.

(Exist.) MDOT Tag - S40°E - 137.01' - 14" Cedar



Signed by D.B. Guthrie

Date 12-22-97

Surveyor's Michigan License No. 22435