

**SURVEY &
REMONUMENTATION**

MAR 13 1998

**1997 Mackinac County Remonumentation Corner
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Mackinac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T42N R 1W	M-2 ✓
	T42N R 1E	A-2
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

RECEIVED & FILED
DIANE FRANK KOVICH
MAY 1997

DEC 31 1997
AM PM
7|8|9|10|11|12|1|2|3|4|5|6

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David B. Guthrie, in a field survey on Dec. 17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4	3		2		1			
3												
4	7	8		9	10		11		12			
5												
6	18	17		16	15		14		13			
7												
8	19	20		21	22		23		24			
9												
10	30	29		28	27		26		25			
11												
12	31	32		33	34		35		36			
13												

A. Description of original monument and accessories and/or subsequent restoration:
1840: G.L.O. Survey by Wm. A. Burt - Set Post and Referenced -
Tamarack 10 / S84W / 23
Tamarack 7 / N61W / 26
1975: L.C.R.C., Liber C, Page 165, Set 1" Pipe
1992: Survey by Neil Hill - Found Rod and Cap in Monument Box.
Liber D Page 138

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997: Remonumentation survey by R.S. Scott Associates, Inc.
Found 1/2" Rod and Cap.
This corner position is compatible with County and local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

ACCEPTED BY THE MICHIGAN COUNTY
SURVEYING BOARD AS A TRUE
ORIGINAL CORNER EVIDENCE
FILED BY _____
12-19-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1997: Placed 3" Mackinac County Cap stamped to identify the corner over 1/2" Iron Rod in Monument Box.
Referenced -
(Exist.) MDOT Tag - S60°E - 77.67' - P.P.
(Exist.) Tag#3920 - N40°W - 95.78' - 12" Maple
(Exist.) MDOT Tag - S70°W - 83.80' - 4" Ash
(Exist.) MDOT Tag - N85°W - 79.16' - 4" Ash



Signed by David B. Guthrie
Surveyor's Michigan License No. 22435

Date 12-22-97