

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	R	_____
	T	R	_____
	T	R	_____
	T	R	_____
2. Property Controlling in Section	S 16	T 42N R 1W	12
	S 16	T 42N R 1W	11
3. Miscellaneous Property in Sec.	S	T R	_____
	S	T R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

11 Sep 24 2002
 12 Sep 23 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (12-Sec. 16) South 1/16 corner. Not established in the original survey. Established and monumented by Ronald Bischer RLS 22428 in 1995 (Liber 394 Page 635).
 (11-Sec. 16) Southwest 1/16 corner. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (12-Sec. 16) Found a 1/2" rebar with plastic cap # 22428 at the proper position and accepted same.
 (11-Sec. 16) Established the corner at the intersection of straight lines connecting opposite 1/16 corners. 1/16 corners 10 and 15 were left unmonumented in this survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(12) Found 1/2" dia. rebar with plastic cap # 22428, flush. Blazed, scribed, and set measuring nails in:	(11) Set 1" IDx36" I.pipe with 4" dia. alum. MDNR cap. Blazed, scribed, and set measuring nails in:
16" Cedar N58W 24.3' "S1/16 8T"	8" Spruce S65E 8.2' "SW1/16 8T"
12" Cedar S87W 17.55' do	6" W.Birch South 21.75' do
10" Cedar S40E 7.55' do	20" R.Pine N87W 45.7' do
12" Cedar N86E 18.5' do	5" Spruce N02E 10.8' do

Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/31/02