

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T 42N	R 1W	F6
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S 16	T 42N	R 1W
	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 23 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6				18		17		15		14		13	
7													
8				19		20		21		22		23	
9													
10				30		29		28		27		26	
11													
12				31		32		33		34		35	
13													


(A) Description of original monument and accessories and/or subsequent restoration: _____ and monumented in 1993 by Ronald Bischer RLS 22428.
 (F6) Center of Section 16. Not established in the original survey. Established and monumented in 1993 by Ronald Bischer RLS 22428 midway and on a straight line between 1/4 corner and Center of Section.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F6) Found and accepted a 1/2" dia. rebar with plastic cap # 22428 at the intersection of 1/4 lines.
 (5-Sec. 16) Found a 1/2" rebar with plastic cap #22428 at the proper position and accepted same.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

(F6) Found 1/2" rebar with plastic cap #22428. Drove a 1"IDx36" I.pipe with 4" alum. MDRR cap over it. Blazed, scribed, and set measuring nails in:	(5) Found 1/2" dia. rebar with plastic cap # 22428, flush. Blazed, scribed, and set measuring nails in:
10" Oak N46E 15.75' "CS 87"	8" Oak N20W 19.05' "N1/16 NBT"
12" Oak N38W 21.45' do	8" M. Birch N13W 24.55' do
6" M. Pine N88W 30.75' do	12" Beech N88E 22.5' do
6" Oak S41W 44.6' do	8" triple Beech S50W 31.2' do
A 2" I.pipe 3ft. a.g. N30W 0.85'. Bearings magnetic. Dist. to nail with tag.	Placed post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/3/02

Register of Deeds Stamp & File Number