

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Mackinac

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>42</u> N	R <u>1</u> W	E6
	T <u> </u>	R <u> </u>	<u> </u>
	T <u> </u>	R <u> </u>	<u> </u>
	T <u> </u>	R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>
	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>
	S <u> </u>	T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Sep 24 2002

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17	●	16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
 (E6) Quarter corner common to Sections 16 & 17. Record corner position, midway and on a line between section corners, was accepted by the Mackinac County Survey Peer Group as the official corner under P.A. 345 of 1990 on 12 Dec 1998. Corner monumented 21 Dec 1998 by Neil Hill RLS 27447. Corner monument: 1" pipe with DNR 4" brass cap. Witnesses: 10" Maple N35W 8.60', 14" Maple N10E 10.27', 10" Maple S85W 13.88', 8" Maple S05W 20.04' (compass bearings, corrected for decl. Distances to double headed nail in the sides of trees). Liber E Page 300, Mackinac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) Recovered the 1998 monument as described, in good condition, and at record bearing and distance from the 1998 witnesses. True courses to the adjacent section corners were found as follows: N 00 deg. 27' 51"E 2652.11' to E5 of record, and S 00 deg. 20' 47"W 2649.02' to E7 of record. Determined that the monument was installed 2.72' West and 1.55' South of the midway position intended in 1998. Removed the 1998 monument and placed a new monument midway and on a straight line between E5 and E7 2650.56' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Set 1"IDx36" I.pipe with 4" dia. cast alum. MDNR cap. Made new measurements to the 1998 witness trees:
 14" Maple N16W 9.25'
 10" Maple N56W 10.0'
 10" Maple S87W 16.85'
 8" Maple S15W 21.8'
 Set post adjacent. Bearings are magnetic. Distances are to a double headed nail in the side of the tree.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 12/3/02