

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 6W


Mackinac COUNTY

DESCRIPTION OF CORNER Meander corner for sections 18-19

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 4-10-62

WITNESSES TO CORNER..... 8" W. Pine (M.C. NBT) S66°E, 65½ links



12" Cedar (M.C. NBT) N29°E, 100 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two original pine B.T.'s bearing N4°W, 70 links, stub 6 foot high and decayed stump N37°E, 59 links. Stub has scribe marks "B.T."

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE July 19, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler