

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 6W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for sections 5-6-7-8

CORNER MONUMENT 1" pipe with 4" brass cap

DATE MONUMENT PLACED AND WITNESSED 9-21-61

WITNESSES TO CORNER..... 6" Red Pine (S8 NBT) S65°E 60 links



16" W. Pine Stump (NBT) S30°W 96 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced by proportionate measure between corners to East and West and from edge of marsh 4.00 chs south. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 14, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler