

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 6W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner for sections 17-18-19-20

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 5-2-62 with E. Eckart, D. F.

WITNESSES TO CORNER..... 9" Cedar (S18 NBT) N79°W, 26½ links



CIRCLE CORNER REGISTERED

8" Cedar (S19 NBT) S25°W, 10 links

9" Cedar (S20 NBT) S78°E, 36½ links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced as set by unknown surveyor about 37 years ago. Found point of old wood post in soil with a cedar 12" N6°E, 24½ links and a Spruce 16" N 10°W, 32 links, marked as witnesses.

Found original meander corner 11.35 chs. west of this corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 29, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler