

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N R. 6W


Mackinac COUNTY

DESCRIPTION OF CORNER Section corner common to sections 7-8-17-18

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 4-25-62

WITNESSES TO CORNER..... 7" Hard Maple (S17 NBT) S 3°E, 11½ links



7" Hard Maple (S8 NBT) N82°E, 13½ links

5" Hard Maple (S7 NBT) N30°W, 29 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportionate distance from corners one mile north; one mile west; one mile south and 3 miles east. No evidence of original corner.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE April 29, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler