

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N. R. 6W


Macinac COUNTY

DESCRIPTION OF CORNER South 1/16 Corner between Secs. 16-17

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 2/24/64 with Forestry Aide Burnis

WITNESSES TO CORNER..... 14" W. Pine (S1/16 BT) N40°W 51 Lts.



7" W. Pine (S1/16 BE) S 06°E 64½ Lts.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was established by placing it midway and on Line between 1/4 Corner to North and Section Corner to South.

SURVEYOR'S SEAL

SIGNED Frank J. Gray DATE 8/1/1964
REGISTERED LAND SURVEYOR