

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> <sup>N.</sup> <del>S.</del> R. <u>6</u> <sup>E.</sup> <del>W.</del>	F-6
2. PROPERTY CONTROLLING IN SECTION <u>16</u>	, T. <u>42</u> <sup>N.</sup> <del>S.</del> R. <u>6</u> <sup>E.</sup> <del>W.</del>	5-Sec.16, 6-Sec.16 8-Sec.16
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>S.</del> R. _____ <sup>E.</sup> <del>W.</del>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-28, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-6 Center Corner of Section 16.
- 5-Sec.16 North 1/16 Corner of Section 16.
- 6-Sec.16 North-East 1/16 Corner of Section 16.
- 8-Sec.16 West 1/16 Corner of Section 16.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- F-6 Placed corner at intersection of lines connecting opposite 1/4 corners.
- 5-Sec.16 Placed corner midway bet. center corner to South and North quarter corner.
- 6-Sec.16 Placed corner at intersection of lines quartering the quarter section.
- 8-Sec.16 Placed corner midway bet. center corner and West quarter corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**


Placed 1" pipe with 4" aluminum cap at all four corners. Bearings:

- F-6 10" S. Maple, S29°W, 8.0' & 10" W. Pine, N38°E, 8.2' & 6" Cedar, N17°W, 15.4'.
- 5-Sec.16 8" Cedar, N35°E, 20.3' & 10" Hemlock, S26°E, 61.3' & 6" R. Maple, S57°W, 32.0'.
- 6-Sec.16 7" Beech, S56°W, 29.1' & 10" Hemlock, N58°E, 13.9' & 12" Hemlock, N40°W, 41.5'.
- 8-Sec.16 14" R. Maple, S19°W, 1.8' & 16" S. Maple, N51°E, 30.4' & 8" R. Maple, N79°W, 37.6'.

SIGNED BY \_\_\_\_\_ DATE 10-9-80  
Billy D. Buckler  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
 REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET