

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Mackinac Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> <sup>N.</sup> <del>S.</del> , R. <u>6</u> <sup>E.</sup> <del>W.</del>	14-Sec.25, 9-Sec.25
2. PROPERTY CONTROLLING IN SECTION <u>25</u>	, T. <u>42</u> <sup>N.</sup> <del>S.</del> , R. <u>6</u> <sup>E.</sup> <del>W.</del>	13-Sec.25
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> <del>S.</del> , R. _____ <sup>E.</sup> <del>W.</del>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-22, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 14-Sec.25 South 1/16 Corner on East side of Section 25.
- 9-Sec.25 East 1/16 Corner of Section 25.
- 13-Sec.25 Southeast 1/16 Corner of Section 25.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 14-Sec.25 Placed corner midway and on line bet. Sec. Cor. to South and 1/4 Cor. to North. Found an Iron Pipe 10.2' South and 3.65' West of Corner. Corner is 20' South of pipe line clearing.
- 9-Sec.25 Witnessed corner set by unknown party.
- 13-Sec.25 Witnessed corner, a 36" "T" Iron set by unknown.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 14-Sec.25 Placed 1" pipe with 4" aluminum cap at corner. Bearings: 8" Oak, N89°W, 12.6' & 8" J. Pine, N15°E, 12.8'.
- 9-Sec.25 36" "T" Iron (found). Bearings: 14" W. Pine, N6°E, 20.7' & 20" W. Pine, S40°W, 7.9' & 7" S. Maple, S60°E, 17.5'.
- 13-Sec.25 36" "T" Iron. Bearings: 5" R. Pine, S7°W, 10.7' & 8" R. Pine, S70°E, 17.3' & 7" R. Pine, N25°W, 7.5'.

SIGNED BY Billy D. Buckler DATE 9-29-80

Billy D. Buckler  
SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET