

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located In:

Corner Code: //

1. Public Land Survey	T	42N	R	6W	I-8
	T	42N	R	6W	K-7
	T		R		
	T		R		
2. Property Controlling in Section	S	13	T	42N R 6W	11
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gerald L. Wiggins, in a field survey on 4-19 & 4-26, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8 East 1/4 Corner of Section 22. Corner set by Lawrence Feindt L. S. Witness's: 10" Cedar, S80°E, 22.22' & 10" Cedar, S10°W, 7.19' & 7" Cedar, N85°W, 12.04'.

K-7 S.W. Section Corner of Section 13. Corner set Billy D. Buckler L.S. on 5-6-68. Witness's: 9" Y. Birch, N1°E, 21.7' & 9" S. Maple, S47°E, 23.3' & 12" S. Maple, S83°W, 6.5'.

11 S.W. 1/16 Corner of Section 13. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 Feindt's monument still in place but all three witness trees have blown over. Marked new witness trees.

K-7 Buckler's monument still in place but Y. Birch has been cut. Marked three new witness trees.

11 Corner set at the center of the S.W. 1/4 of Section 13.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I-8 Placed a DNR Monument beside 1" Pipe. 10" Cedar, N49°W, 18.2' & 8" Cedar, N11°W, 16.2' & 8" Cedar, N32°E, 20.1' & 8" Cedar, N46°E, 49.0'.

K-7 DNR Monument. Buckler's Witness's and marked 10" W. Birch, S18°W, 9.5' & 5" Maple, N68°W, 25.7' & 14" W. Birch, N13°W, 27.9'.

11 DNR Monument. 10" R. Maple, N42°E, 39.3' & 6" Beech, S83°E, 42.3' & 8" Beech, S22°W, 9.2' & 12" Beech, N9°E, 15.7'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12	13	14	15	16	17	18	19
5													
6	13	14	15	16	17	18	19	20	21	22	23	24	25
7													
8	19	20	21	22	23	24	25	26	27	28	29	30	31
9													
10	25	26	27	28	29	30	31	32	33	34	35	36	37
11													
12	31	32	33	34	35	36	37	38	39	40	41	42	43
13													

Signed by Gerald L. Wiggins Date 9-13-90
 Surveyor's Michigan License No. 23521



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 22, 1971
 REVISED MAY 14, 1976
 REVISED JAN. 1993