

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MACKINAC</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>42N</u> R <u>6W</u>	<u>CA</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>8</u> T <u>42N</u> R <u>6W</u>	<u>11</u>
	S <u>8</u> T <u>42N</u> R <u>6W</u>	<u>12</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on October 30, 1991, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C4) CORNER REESTABLISHED AND RECORDED UNDER ACT 74, P.A. 1970 BY BILLY D. BUCKLER IN 1980 AS A 1" PIPE WITH 4" ALUM. CAP SET MIDWAY AND ON LINE BETWEEN ADJACENT SECTION CORNERS. BUCKLER'S BT'S ARE: 6" S. MAPLE N11W 17.1'; 24" N. PINE S15E 34.6'; 12" BEECH S61E 36.4'.

(11) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. FOUND NO SUBSEQUENT RECORD.

(12) CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. FOUND NO SUBSEQUENT RECORD.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C4) FOUND AND ACCEPTED A 1" PIPE WITH 4" ALUMINUM MI DEPT OF CONSERVATION TABLET IN ACCORD WITH ALL OF BUCKLER'S BT'S.

(11) FOUND NO MONUMENTATION AT THIS POSITION. ESTABLISHED CORNER AT THE INTERSECTION OF STRAIGHT LINES CONNECTING OPPOSITE 1/16 CORNERS. CORNERS (8) AND (12) BEING MONUMENTED, (10) AND (15) BEING COMPUTED MIDWAY AND ON A STRAIGHT LINE BETWEEN ADJACENT SECTION AND 1/4 CORNERS. AT THE POSITION FOR THE CORNER, I PLACED A 1"x30" PAINTED IRON PIPE CAPPED WITH A 4" DIA. CAST ALUMINUM MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET STAMPED TO IDENTIFY THE CORNER.

(12) FOUND NO MONUMENTATION AT THIS POSITION. ESTABLISHED CORNER EQUIDISTANT AND ON A STRAIGHT LINE BETWEEN D5 AND D4, D4 BEING AN UNMONUMENTED POSITION COMPUTED AS THE INTERSECTION OF STRAIGHT LINES CONNECTING OPPOSITE 1/4 CORNERS. AT THE POSITION FOR THE CORNER, I PLACED A 1"x30" PAINTED IRON PIPE CAPPED WITH A 4" DIA. CAST ALUMINUM MICHIGAN DEPARTMENT OF NATURAL RESOURCES TABLET STAMPED TO IDENTIFY THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C4) FOUND 1" PIPE WITH 4" ALUMINUM TABLET. N63E 28.0' SE FACE 14" BEECH; N11W 17.12' E. FACE 9" R. MAPLE (OBT); S15E 34.98' W. FACE 26" W. PINE (OBT); S61E 36.78' N. FACE 13" BEECH (OBT); SOUTH 1" 6" WOOD POST SQUARED AND SCRIBED; N'LY 326' SET LOCATION POSTER ON N. FACE SQUARED 12" R. MAPLE 31' S. OF C/L E-W TRAIL. DISTANCES ARE TO NAILS AND TAGS SET IN FACES NOTED. OBT'S WERE FND SCRIBED AT BASE AND WERE SCRIBED AT BH. NBT'S WERE SCRIBED AT BASE AND BH.	(11) 1" PIPE WITH MDNR TABLET. N73W 12.3' S. FACE 9" R. MAPLE; N12W 10.67' E. FACE 11" R. MAPLE; N55E 29.18' N. FACE 8" R. MAPLE; S04E 24.74' E. FACE 11" R. MAPLE. DISTANCES ARE TO NAILS SET IN BRASS MDNR REF. TAGS PLACED ON FACES NOTED. ALL BT'S WERE BLAZED AND SCRIBED AT BASE AND BH.	(12) SET 1" PIPE WITH MDNR TABLET. S87W 12.78' N. FACE 10" BALSAM; N48W 10.30' SW FACE 7" R. MAPLE; N47E 4.74' N. FACE 7" R. MAPLE; S09W 9.17' W. FACE 14" R. MAPLE; SOUTH, SQUARED MAPLE POST ADJACENT. DISTANCES ARE TO NAILS SET IN BRASS MDNR REF. TAGS PLACED ON THE FACES NOTED. ALL BT'S WERE BLAZED AND SCRIBED AT BASE AND BH.
--	--	---

Signed by Stephan J. Szyszkoski Date 11-25-91

Surveyor's Michigan License No. 3398

